



國家同步輻射研究中心
National Synchrotron Radiation Research Center

The construction of an auto-tuning girder system for TPS storage ring

Tse-Chuan Tseng

NSRRC, Taiwan

7th MEDSI , Oct. 19, 2012

NSRRC



Outline

1. Storage ring girder system design
2. Manufacturing and inspection
3. 1/24 ring section mockup girder system installation, measurements and testing
4. System assembling processes
5. Summary




Taiwan Photon Source

Parameters of TPS Synchrotron Facility

Energy	3 GeV
Beam Current	500 mA at 3 GeV
C of the Storage Ring	518.4 m (h = 864)
C of the Booster	496.8 m (h = 828)
Cells	24-cell DBA
Straight Sections	12 m x 6 ($\sigma_v = 9.8 \mu\text{m}$, $\sigma_h = 165.1 \mu\text{m}$) 7 m x 18 ($\sigma_v = 5.1 \mu\text{m}$, $\sigma_h = 120.8 \mu\text{m}$)
Emittance	1.6 nm·rad at 3 GeV (Distributed dispersion)
RF frequency	499.654 MHz
Critical Energy	7.13 keV (dipole)
Energy Loss/turn	853 keV (dipole)

Brightness of Synchrotron Light Sources



國家同步輻射研究中心
National Synchrotron Radiation Research Center

Design goals of the girder system for TPS

- Firm support and precise positioning of magnets ($30\mu\text{m}$ relative to the girder)
- High nature frequency above 30 Hz
- Alignment accuracy within 0.1mm

Traditional alignment network simulation reveals an accuracy of 0.15mm typically. It needs to be iterated several times to reduce to 0.1mm and is also time consuming

- Precise resolution (μm)


Manual adjustment mechanism is of poor resolution and time consuming

- Toward whole ring automatic alignment (optional)


**How to align the girders precisely and quickly with less manpower?
Considering the deformation of the floor and limited space in the tunnel also frequent earthquakes in Taiwan .**

A 6-axis motorized adjusting mechanism is proposed!

One girder system configuration




Cam mover type mechanism modification and adjusting algorithm




A 3 grooves type kinematic mounting modification to 6 stands girder design


- To determine how to adjusting the girder in each direction by movers directly is not easy.
- An algorithm had been established to transfer the directional adjusting magnitude to the motor's steps.
- Two coordinate systems are to be established at girders and movers separately, from the rigid body assumption, the adjustment of center position of each ball can be calculated.



Modification of point contact type cam to line contact to reduce stress




- Kinematic mounting situation preserved.
- The contact position of the ball and the cam remains the same for adjusting algorithm.
- the contact situation changes from point contact to line contact,
- the stress is reduced drastically to 12.4% and far beyond the elastic limitation of the cam.



harmonic drive
constant torque : 35 kg.m

Sensors System



72 Leica Nivel220 tilting sensors




440 Heidenhain ECN425 rotary encoder



400 Heidenhain Acanto AT1218 absolute length gauge




Laser positioning system






Architecture

- Fiber Laser
- PSD
- Beam Splitter Module
 - Optics
 - Mechanism
- Isolation tubes and relative parts




Laser Positioning System



- PSD and Fiber Laser
 - Purchased, received & inspected
- Beam Splitter (PV(rms) $<1/20\lambda$, parallelism $<0.5s$)
 - Purchased, received & inspecting
- Beam Splitter Module
 - Delivering and inspecting



Auto Seq	
Auto Seq Max Count:	10
Auto Seq Delay:	00:00:00
Auto Seq Count:	
PV	0.053 wave
rms	0.010 wave
Power	-0.026 wave
Size X	27.0 mm
Size Y	27.0 mm
Filter:	Off
	Trimmed: 0
Aperture ID (%)	



Girder Measurement and Assembly



- All the girders are examined by using laser interferometer, autocollimator and laser tracker
- Straightness measurement of assembling reference channel on each girder is around 8~12um
- The deviation of the ball center of transfer unit is less than 0.3mm

Pedestal and manufacturing parts measurement and assembly




- All components were measured with CMM stage and arms, laser tracker and precision gages to make sure within spec before assembling.
- The movers also being performed with life cycling test



Sensor Module Assembly



Touch sensor module



Tilting sensor module


Lens adjusting
with a toolkit




Lens fine_tune



PSD alignment



Lens module adjustment



Adjusting Screw (pitch: 0.2mm)

PSD module



Control system



Delivered and assembled into the Racks

Mockup System Installation Measurements and Testing




3 mockup system had been installed
at the rental fab. for interface and
assemblage testing



Natural Frequency and damping testing




One girder section was installed with dampers and locking system for testing



The 1st NF can be raised to 33 with locking mechanisms



	pedestal (x 10 ⁻⁵ mm)	ground (x 10 ⁻⁵ mm)	
	4~100Hz	4~100Hz	AMP
w/o damping X	5.85	5.52	1.060
Soft damping X	7.86	8.67	0.907
stiff damping X	6.78	6.78	1.000
w/o damping Y	6.71	6.68	1.004
stiff damping Y	6.95	7.64	0.910
Soft damping Y	8.23	8.26	0.996

Amplification with damper



The Peak amplitude is reduced with dampers


Girder assembled with magnets transportation test



Since the girder and magnets will be assembled in the rental fab., a transportation test was performed. With a air-cushion truck and speed less than 20 km/hr, the deviation at the magnet button is less than 5 μm


Girder System Assembling Processes

- Almost all components have been delivered and sub-assembled then the girder with sensors system assemblage start.
- The procedures include:
 1. Measure distances between reference holes on one girder with a laser interferometer
 2. Measure distances between reference holes on adjacent girders with a encoder rule
 3. Touch sensor module assemblage
 4. PSD module assembling, partially auto-alignment processing and sensor's data acquisition



8 girder sections (24 girders) were finished till now (2012/10)

Assembled Magnet Center Deviation Measurement PSD system







In order to measure the center deviations of the magnets on one girder, a laser PSD system were set up and under testing now



Auto-Alignment Experiment

With the 1/12 ring assemblage (2 bending sections with one straight section) configuration, An auto-alignment Experiment was carried out




- The laser tracker is utilized to be the feedback in the system.
- It is connected to control system by network.

- **Sensor measurement errors : Laser tracker 21 μm , Touch sensor 1.6 μm , PSD 3.85 μm , Nivel 2 urad**
- **Convergence: X(19 μm) , Z(60 μm)**
- **Repeatability: X(16 μm) , Z(4 μm)**
- **Systematic error (1mins) : 27μm (max)**

The laser tracker control fiducial points network

- Survey targets are installing on the wall and floor of the tunnel and the distance between two survey targets of the storage ring is about 10 m.
- 48 survey holes on the shielding wall , top of the frontend outlet window, and the survey targets are installed on the two side of the wall.
- The survey network connects the survey of the storage ring and the experimental area by the view holes.



Survey target of TPS



The storage ring and survey holes

Pedestals transportation into tunnel



Pedestals were transported into tunnel and scheduled to be half-ring installed at November 2012



Summary

1. Most components of the TPS girder system were delivered and fully checked to meet the specification.
2. Sub-system assemblage were finished and function tested.
3. System assemblage with sensors calibration data accumulation is under going and 1/3 ring were finished.
4. A Laser PSD system to measure the center deviations for magnets assembled on a girder was setup and under testing.
5. A preliminary auto-alignment testing had been carried out and the results shows good conservation and repeatability.
6. A thorough survey network has been established and used to monitor the building construction and the set out for the pedestals installation is underway.
7. A half ring girder installation without magnets is scheduled in 2012.



Thanks for Attention!

