


Hall probe bench prototype

for closed magnetic structures

ALBA Synchrotron Light Source, Engineering division, Transversal section

Llibert Ribo, Carles Colldelram, Liudmila Nilkitina, Pep Campmany





- Requeriments
- Concept
- Validation
- Prototype Specifications
- Conceptual design: and dimensions
- Materialization and Description
- FEA
- Mounting
- Results



Requirements








Requeriments

- Upgrade to the ID lab to measure closed magetic structures
- Long longitudinal Measuring ranges (up to 3 m)
- Vertical and transversal direction scans
- Small Guidance error on positioning the hall sensor (order of 0,05 mm)
- Very small angular deviations (order of 0,05 mrad)



Simple Idea

- Hall sensor attached on a string tensioned on a C shaped arc structure
- The string is passing through the closed magnetic strucure
- The arc is moved by an accurate positioner



THIS CAN WORK??...

- We are able to materialize that arc and move it with a positioner of a precision level of a machining tool
- We will need a lot of space and we have it
- Is a string stable enough once is tensioned?




Validation

The Vibrating string

A string under tension has a mode of vibration on the first harmonic which frequency depends on the **vibrating lenght**, the **tension** and the **linear mass**.



$$f = \frac{1}{2*L}*\sqrt{\frac{T}{\mu}}$$




When this is excited, will have direct impact on the positioning accuracy of the hall sensor.

Calculation of the 1st harmonic vibration

- L ~ 4000 mm
- Area 24x1,4 mm2
- Material Pultruded carbon fiber d=1600Kg/m3
- Elastic limit 2800 Mpa

$$T = 7,5kN \rightarrow f = 55 \text{ Hz} \rightarrow \text{stress} = 223 \text{ Mpa}$$

At ALBA environmental low frequencies are considered under 30 Hz This value is taken as a reference when designing in a safe margin







Validation

Empirical exercice

- Evaluate fundamental frequency modes of a tensioned strip of the same section calculated previously
- Inducing external excitation for amplification checking
- Very simple exercise to confirm the analytical values of the frequencies and the amplitude







Specification and parts

Ranges.

X: ±125 mm Z: ±50 mm Y: 1200 mm

Chamber allowance ("stay

clear" area) = 600 mm

Longitudinal POSITIONING ERROR

dX, dY, dZ < 0.05 mm

Angular POSITIONING ERROR


Roll d α , Pitch d β < 0,05 mrad Yaw d φ < 0,1 mrad

Repeatability

X, Y, Z ≤ 0,03 mm


Speed


Y ~15 mm/s





Dimensions







Materialization: arc structure



Strip dimensioning

- Area 16x1,4 mm2
- Vibrating length 2600 mm
- d = 1600 Kg/m3
- Tensioning force 0.5 TN





Results

- Stress = 223 Mpa
- Security factor = 13
- f1 = 71 Hz
- Elongation \sim 4 mm


Arc structure


- Aluminium profile structure
- Two tensioning blocks one with stretching gauge
- Mass arround 400 Kg













Z stage

- Double flexure system on a granite block
- Compact design: with a single step Z&pitch
- Allows Z range of 100 mm and tilt about 0,2°
- Flexures on high modulus material
- Preloaded guiding system and grinded spindles
- Movement for each flexure is encoded
- Mass of that assembly arround 1.2 Tn









XY stage

- X stage 2 actuators are implemented to avoid rotation on the vertical axis due to the long beam
- Y stage: Measurement axis: All mounted on a granite block
- Preloaded roller and matched guides
- Separation between those guides affect on the vertical accuracy
- Mass of the XY stage 5 Tn











FEA calculation

























XY stage

- Verification of the components with alignment and metrology group
- Big granite block is aligned flat on respect to the floor.


XY stage

- Interface plate fitted in top. Checking the slots where the transversal guides are.
 Grinding was corrected.several times
- Very accurate alignment of the sets of linear guides




Mounting II





Z stage

- Hollowed granite block is located on top of the XY stage
- The assembly is stopped to test the motors and perform some measurements to test the actuator







Mounting III





Arc structure


- Stretching system
- Carbon fiber is cutted by water
- The assembly is stopped to test the motors and perform some measurements to test the actuator
- C structure and stretching system are mounted in parallel
- Carbon fiber is tensioned up to 1Tn


















Results: Z Scan













ALBA Angle evolution






ROLL EVOLUTION MOVING ALONG Y AXIS





Vibration static

















Vibration on movement















Next steps and Conclusions



Next

- Finish the measurements (X scans and repeatability) and prepare a performance report for the ID group is needed to inform the magnetic measurement group.
- Hall sensor integration and first measurements with a calibration magnet

Conclusions

- · Specifications are almost guaranteed
- It can work for very narrow gap closed structures up to open conventional dipoles
- That solution tooks a big space for the operation range
- If this short prototype suceed, a 3 m range bench can be consiereded using this concept



