


# LCLS-II – Project and Engineering Challenges

## MEDSI 2014, Melbourne

Nicholas M. Kelez 10/21/2014

- LCLS-II Project Overview
- Accelerator Components and Engineering Challenges
- Future Outlook

# LCLS Timeline



1992: Proposal (Pellegrini), Study Group(Winick)

1994: National Academies Report

1996: Design Study Group (M. Cornacchia)

1997: BESAC (Birgeneau) Report

1998: LCLS Design Study Report

1999: **BESAC (Leone) Report**

2000: LCLS-First Experiments (Shenoy & Stohr)

2001: DOE Critical Decision 0

2002: LCLS Conceptual Design Report and DOE Critical Decision 1

2003: DOE Critical Decision 2A

2004: DOE 20-Year Facilities Roadmap

2005: DOE Critical Decision 2B and 3A

2006: DOE Critical Decision 3B

2009: First Light, 10 April 2009

2009: First Light to First Instrument August 19 2009

2009: First Instrument Commissioned September 12, 2009

2009: LCLS-II Critical Decision 0

2010: **LCLS CD-4 June 2010**

2011: LCLS-II Critical Decision 1 Review April 26, 2011

2011: LCLS-II Critical Decision 3a Review Dec 6, 2011

2012: Final Instrument Commissioned April 4, 2012


2012: LCLS-II Critical Decision 2 Review Aug 21, 2012

2013: **BESAC Subcommittee Report July 25, 2013**

2014: LCLS-II Critical Decision 1 Review Feb 4, 2014

2014: **LCLS-II CD1 Aug 22, 2014**

2015: LCLS-II Critical Decision 2 Review Feb 2015 ?




**BESAC Subcommittee  
on  
Future Light Sources**

Presentation to BESAC, July 25, 2013




# Linac Coherent Light Source Facility

First Light April 2009, CD-4 June 2010





# Linac Coherent Light Source II — phase1





# BESAC Subcommittee Report: July 25, 2013

- Committee report & presentation to BESAC:
  - “It is considered essential that the new light source have the pulse characteristics and **high repetition rate** necessary to carry out a broad range of coherent “pump probe” experiments, in addition to a sufficiently broad photon energy range (**at least ~0.2 keV to ~5.0 keV**)”
  - “It appears that such a new light source that would meet the challenges of the future by *delivering a capability that is beyond that of any existing or planned facility worldwide is now within reach. However, no proposal presented to the BESAC light source sub-committee meets these criteria.*”
  - “The panel recommends that a decision to proceed toward a new light source with revolutionary capabilities be accompanied by a robust R&D effort in accelerator and detector technology that will maximize the cost-efficiency of the facility and fully utilize its unprecedented source characteristics.”

# Project Collaboration



- 50% of cryomodules: 1.3 GHz
- Cryomodules: 3.9 GHz
- Cryomodule engineering/design
- Helium distribution
- Processing for high Q (FNAL-invented gas doping)




- 50% of cryomodules: 1.3 GHz
- Cryoplat selection/design
- Processing for high Q



- Undulators
- $e^-$  gun & associated injector systems




- Undulator Vacuum Chamber
- Also supports FNAL w/ SCRF cleaning facility
- Undulator R&D: vertical polarization



- R&D planning, prototype support
- processing for high-Q (high Q gas doping)
- $e^-$  gun option

## A New LCLS-II Project Redesigned in Response to BESAC


<b>Accelerator</b>	<b><u>Superconducting linac</u>: 4 GeV</b>
<b>Undulators in existing LCLS-I Tunnel</b>	New variable gap (north) New variable gap (south), replaces existing fixed-gap und.
<b>Instruments</b>	Re-purpose existing instruments (instrument and detector upgrades needed to fully exploit)
<b>Total Project Cost</b>	\$965M





- New linac based on 1.3 GHz SCRF with MHz beam rate
  - 1.3 GHz technology well established around the world
  - Similar to LCLS with laser heater, harmonic linearizer and dual bunch compressor (and option for third compressor at linac end)
  - Link into existing LCLS beamlines
- Dual variable gap hybrid undulators to cover energy range
  - Self-seeding in both HXR and SXR undulators with options for additional photon phase space control
- Leverage partner labs and extensive work on NGLS, NLS, EU-XFEL, ILC and LCLS-II<sub>Phase I</sub> to develop conceptual design
  - Project definition occurred very rapidly (fall of 2013)

# LCLS-II Accelerator Layout and Modifications



- New Injector, SCRF linac, and extension installed in Sectors 0-10
- Use existing Bypass line from Sector 10 → Beam Switch Yard (BSY)
- Re-use existing high power dump in BSY and add magnetic kicker to direct beams to dump, SXR, or HXR
- Re-use existing transfer line (LTU) to HXR; modify HXR dump
- Construct new LTU to SXR and new dump line



# Linac Coherent Light Source II

Injector @  
0-km point

SCRF Linac  
sector 0-10


Bypass LCLS Linac  
In PEP Xport Line  
(extended)

SXR, HXR Undulators

Near Experiment Hall

X-ray Transport  
Optics/Diagnostics

Far Experiment Hall





# LCLS-II (SCRF) Baseline Parameters


Parameter	symbol	nominal	range	units
Electron Energy	$E_f$	<b>4.0</b>	2.0 - 4.14	GeV
Bunch Charge	$Q_b$	<b>100</b>	10 - 300	pC
Bunch Repetition Rate in Linac	$f_b$	<b>0.62</b>	0 - 0.93	MHz
Average $e^-$ current in linac	$I_{avg}$	<b>0.062</b>	0.0 - 0.3	mA
Avg. $e^-$ beam power at linac end	$P_{av}$	<b>0.25</b>	0 - 1.2	MW
Norm. rms slice emittance at undulator	$\gamma\epsilon_{\perp-s}$	<b>0.45</b>	0.2 - 0.7	$\mu\text{m}$
Final peak current (at undulator)	$I_{pk}$	<b>1000</b>	500 - 1500	A
Final slice E-spread (rms, w/heater)	$\sigma_{Es}$	<b>500</b>	125 - 1500	keV
RF frequency	$f_{RF}$	<b>1.3</b>	-	GHz
Avg. CW RF gradient (powered cavities)	$E_{acc}$	<b>16</b>	-	MV/m
Avg. Cavity Q0	$Q0$	<b>2.7e10</b>	1.5 - 5e10	-
Photon energy range of SXR ( <b>SCRF</b> )	$E_{phot}$	-	<b>0.2 - 1.3</b>	keV
Photon energy range of HXR ( <b>SCRF</b> )	$E_{phot}$	-	<b>1 - 5</b>	keV
Photon energy range of HXR ( <b>Cu-RF</b> )	$E_{phot}$	-	<b>1 - 25</b>	keV




# LCLS-II SASE Performance:

## Photons/Pulse

## Average Brightness





Calculated X-ray pulse energies versus photon energy for the CuRF linac (blue) and the similar curve for the existing LCLS (black).



Performance Measure	Threshold	Objective
Variable Gap Undulators	2 (SXR & HXR)	2 (SXR & HXR)
<b>Super Conducting Linac Based FEL System</b>		
Super Conducting Linac Electron Beam Energy	3 GeV	≥ 4 GeV
Super Conducting Linac Repetition Rate	50 kHz	1,000 kHz
Super Conducting Linac Charge per Bunch	0.02 nC	0.1 nC
Photon Beam Energy Range	0.25-2 keV	0.2-5 keV
High Repetition Rate Capable End Stations	≥ 1	≥ 3
FEL per-pulse intensity on-axis	10X spontaneous	>10 <sup>11</sup> photons in 10 <sup>-3</sup> BW
<b>Normal Conducting Linac Based FEL System</b>		
Normal Conducting Linac Electron Beam Energy	13 GeV	15 GeV
Normal Conducting Linac Repetition Rate	120 Hz	120 Hz
Normal Conducting Linac Charge per Bunch	0.1 nC	0.25 nC
Photon Beam Energy Range	1-8 keV	1-25 keV
Low Repetition Rate Capable End Stations	≥ 2	≥ 3
FEL per-pulse intensity on-axis	10X spontaneous @ 8 keV	>10 <sup>12</sup> photons in 10 <sup>-3</sup> BW @ 13 keV


# SASE and Seeding - Building on LCLS Experience



- Hard X-Ray Source:
  - 1-5 keV w/ 4 GeV SC linac
  - Up to 25 keV with LCLS Cu Linac
- Soft X-Ray Source:
  - 250 eV-1.3 keV w/ 4 GeV linac
  - 200 eV requires <4 GeV




# Injector Baseline Layout



- CW (up to 1 MHz),  $0.4 \mu\text{m}$  emittance @100pC
- Major injector components:
  - NC 185.7 MHz RF gun
  - $\text{Cs}_2\text{Te}$  cathode; UV/IR lasers for cathode/laser heater
  - NC 1.3 GHz buncher; two solenoids
  - SC 1.3 GHz 8-cavity CM (energy up to 100 MeV)

# The LBNL VHF RF Gun

The Berkeley **normal-conducting** scheme satisfies and often overcomes all the X-FEL requirements.



J. Staples, F. Sannibale, S. Virostek, CBP Tech Note 366, Oct. 2006


K. Baptiste, et al, NIM A 599, 9 (2009)

Frequency (7 <sup>th</sup> 1.3 GHz sub-Harmonic)	186 MHz
<b>Operation mode</b>	<b>CW</b>
<b>Gap voltage</b>	<b>750 kV</b>
<b>Field at the cathode</b>	<b>19.47 MV/m</b>
$Q_0$ (measured)	26500
Shunt impedance	6.5 M $\Omega$
RF Power @ $Q_0$	100 kW
Peak surface field	24.1 MV/m
<b>Peak wall power density</b>	<b>25.0 W/cm<sup>2</sup></b>
Accelerating gap	4 cm
Diameter/Length	69.4/35.0 cm
<b>Operating pressure</b>	<b><math>\sim 10^{-10}</math>-<math>10^{-9}</math> Torr</b>

- At the **VHF frequency**, the cavity structure is large enough to withstand the heat load and **operate in CW mode** at the required gradients.
- Also, the **long  $\lambda_{RF}$**  allows for large apertures and thus for **high vacuum conductivity**.
- Based on **mature and reliable normal-conducting RF and mechanical technologies**.

# LCLS-II 1.3 GHz Cryomodule

Baseline 16 MV/m with  $Q_0 = 2.7 \times 10^{10}$   
CM allows 150 Watts max cooling  
→ 20 MV/m gradient @  $2.7 \times 10^{10}$   
or 16 MV/m @  $1.8 \times 10^{10}$



Total length ~12.2 m Nearly the final LCLS-II cryomodule design


Cryomodules similar to EuXFEL with mods for CW operation  
50% production led by FERMI  
50% production led by J-LAB




# SCRF Linac in SLAC Tunnel

SLAC Linac Tunnel: 11 wide x 10 feet high - It will be a tight fit!


Plans for  
installation and  
servicing under  
development



# Cryogenic Work Scope




# LCLS-II Undulator Layout and Self Seeding





# LCLS-II Segment and Break Section Layout.



**Layout shown for two individual undulator segments and three break sections for the HXR and SXR undulator lines.**


**Radiation damage to magnetic material is a serious concern**

- e-beam collimation and halo control is critical**
- Program for monthly monitoring planned**

# Key Undulator Tolerances

Parameter	HXU	SXU	Unit
$\Delta K_{eff}/K_{eff}$	$\pm 2.3 \times 10^{-4}$	$\pm 4.4 \times 10^{-4}$	
$\Delta y_{align}$	$\pm 80$	$\pm 150$	$\mu m$
$\Delta x_{align}$	$\pm 400$	$\pm 400$	$\mu m$
First field integral range I1Bx, I1By	$\pm 40$	$\pm 40$	$\mu Tm$
Second field integral range I2Bx, I2By	$\pm 50$	$\pm 50$	$\mu Tm^2$
Period error (rms)	$< 25$	$< 25$	$\mu m$
Maximum Phase Shake	$\pm 5$	$\pm 5$	degXray
Integrated sextupole field component	$< 6.4 \times 10^{-4}$	$< 3.4 \times 10^{-4}$	$mm^{-2}$
Yaw error between strongbacks	$\pm 1.0$	$\pm 1.0$	mrad
Pitch error between strongbacks	$\pm 0.035$	$\pm 0.175$	mrad
Roll error between strongbacks	$\pm 1.75$	$\pm 1.75$	mrad
Environmental Field Error	$\pm 0.1$	$\pm 0.1$	G


# Variable Gap Hybrid Undulators – Baseline





Two concurrent undulator R&D programs being pursued:

- Superconducting undulator (SCU) - combined Argonne/Berkeley effort
- Horizontal gap – vertically polarizing undulator (VPU) at Argonne




Argonne 0.8-meter VPU  
test segment

Plan to have a 3 meter  
prototype in fall 2014

E. Gluskin, S. Prestemon, et al

# HGVP undulator prototype

Full scale prototype with compensated beam displacement






# Future Outlook - Facility Expansion Options

SLAC has extensive infrastructure that will allow expansion

- New tunnels are possible north and south of existing LCLS tunnel (complete design for LCLS-II<sub>Phase I</sub>) and could be optimized for long, high pulse energy, hard X-ray FEL's
- Original research halls: ESA and ESB suitable for shorter, soft X-ray FEL's should they be developed



# Acknowledgements



**The entire LCLS-II project team: J. Galayda, T. Raubenheimer, H.D. Nuhn, T. Peterson, D. Cocco**

